No.	Details	Per	Rate	Quantity	Cost
	(7) Plastering with surki mortar	Sq.		6·16	
	(8) Steel pipes, $\frac{1}{8}$" thick	lbs.		89·20	
	(9) Earthwork excavating, etc.	Rs.	Lump	sum	
17	*Foot bridge at* 5/3.				
	(1) Concrete in surki mortar	C. ft.		91	
	(2) Burnt stone in surki mortar	,,		193	
	(3) Stone slabs, 6" thick	S. ft.		36	
	(4) Pointing with surki mortar	Sq.		0·80	
	(5) Rough stone dry work	C. yd.		6	
	(6) Earthwork excavation, etc.	Rs.	Lump	sum	
18	*Relieving weir at* 1/4; 30 *feet length.*				
	Details as per above relieving weir at 8/1 of left channel—				
19	*Road bridge at* 1/4 ; 1 *vent* 5'X9"				
	(1) Concrete in surki mortar	C. ft.		377	
	(2) Burnt stone in mortar	,,		965	
	(3) Pointing with surki mortar	Sq.		6·50	
	(4) Stone slabs. 6" thick	S. ft.		258	
	(5) Do 3" do	,,		49	
	(6) Rough stone dry work	C. yd.		6	
	(7) Earthwork excavation	Rs.	Lump	sum	
	(8) Guard stones	No.		4	
20	Extra cost for double banks near the sites of aqueducts, syphons, etc.	Rs.	Lump	sum	

Notice dated 19*th February* 1912.

Applications or tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 31st March 1912, for the right of quarrying and removing about 12,000 C. yds. of stone from the burnt stone quarry in front of the New High School and opposite the Central College. The depth of stone to be removed is approximately 15 feet from the present summit of the rock and whole of this should be removed to one uniform level, by the end of June 1913.

Applicants should state the rate they are willing to pay for quarrying and removing this stone. The stone quarried will be measured up (no deductions for interstices) as often as is required and the value of same at accepted rates must be paid before removal.

2. Applicants may also state the rate at which they will quarry and supply the stone to this department for the below mentioned purposes:—

(i) Road metal of 1½ inches ... ... Per C. yd.

(ii) Building stones of sizes stacked in heaps ... ... Do

(*N. B.*—Deductions will be made for interstices according to the nature of the stacking.)

(iii) Slabs ... ... Per C. ft. for various thicknesses.

3. Each application must be accompanied by a deposit of Rs. 100 in cash or notes as earnest money.

H. D. RICE,
Executive Engineer.

KADUR DIVISION.

Dated 22*nd February* 1912.

The attention of the public is invited to the notification published in the *Mysore Gazette* dated 29th February 1912, calling for tenders for constructing a Male Lock-up building in the compound of the existing Jail at Chikmagalur, Kadur District.

R. S. NAVARATNA,
Executive Engineer.